BRUHAT BANGLORE MAHANAGARA PALIKE

DASARAHALLI-ZONE

T.DASARAHALLI-SUB-DIVISION.

Name of Work: Road and Footpath maintenance in ward no.15 in Dasarahalli

Est Cost:5.00 Lakhs

ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ

ಸಹಾಯಕ ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರ ಕಛೇರಿ

ದಾಸರಹಳ್ಳಿ ಉಪ-ವಿಭಾಗ ದಾಸರಹಳ್ಳಿ ವಲಯ, ಮಾರಮ್ಮ ದೇವಸ್ಥಾನದ ಹತ್ತಿರ, ಬಾಗಲಗುಂಟೆ

~~~~ ಅಂದಾಜು ಪಟ್ಟಿಯೊಂದಿಗಿನ ವರದಿ ~~~~

ಕಾಮಗಾರಿಯ ಹೆಸರು: – Road & Footpath Maintenance in ward no 15 in dasarahalli.

ಲೆಕ್ಕ ಶೀರ್ಷಿಕೆ :– 2019–20 ನೇ ಸಾಲಿನ ಬಿಬಿಎಂಪಿ ಪಿ ಕೋಡ್–3296, 14th Finance Work

****

ದಾಸರಹಳ್ಳಿ ಉಪ ವಿಭಾಗ ವಾರ್ಡ್ ನಂ.15ರ ವ್ಯಾಪ್ತಿಯಲ್ಲಿ 2019–20ನೇ ಸಾಲಿನ ಪಾಲಿಕೆ ಅಯವ್ಯಯದ ಪಿ ಕೋಡ್– 3296 ಲೆಕ್ಕ ಶೀರ್ಷಿಕೆ ಅಡಿಯಲ್ಲಿ ಮೇಲಿನ ಕಾಮಗಾರಿಯ ಜಾಬ್‌ಕೋಡ್ ಸಂಖ್ಯೆ: 015–20–000081ರಲ್ಲಿ ರೂ. 5.00 ಲಕ್ಷಗಳಿಗೆ ಅನುಮೋದನೆಗೊಂಡಿರುತ್ತದೆ.

ಬಿ.ಬಿ.ಎಂ.ಪಿ ವಾರ್ಡ್ ನಂ–15ರ ವ್ಯಾಪ್ತಿಯಲ್ಲಿನ ರಸ್ತೆ ಮತ್ತು ಪದಾಚಾರಿ ಮಾರ್ಗಗಳನ್ನು ಅಬಿವೃದ್ಧಿ ಪಡಿಸಲು ಸಾರ್ವಜನಿಕರು ಕೋರಿರುತ್ತಾರೆ. ಅದರಂತೆ, ಪಾಲಿಕೆ ಸದಸ್ಯರು ವಾರ್ಡ್ ನಂ–15ರ ವ್ಯಾಪ್ತಿಯಲ್ಲಿನ ರಸ್ತೆ ಮತ್ತು ಪದಾಚಾರಿ ಮಾರ್ಗಗಳನ್ನು ಅಬಿವೃದ್ಧಿ ಪಡಿಸಲು ಸೂಚಿಸಿರುತ್ತಾರೆ ಹಾಗೂ ರಸ್ತೆ ಮತ್ತು ಪದಾಚಾರಿ ಮಾರ್ಗಗಳನ್ನು ಅಬಿವೃದ್ಧಿ ಪಡಿಸುವುದು ತುಂಬಾ ಅವಶ್ಯಕವಾಗಿರುತ್ತದೆ. 2019–20ನೇ ಸಾಲಿನ ಬಿಬಿಎಂಪಿ ಆಯವ್ಯಯದಲ್ಲಿ ಪಿ–3296ರಲ್ಲಿ ರೂ.5.00 ಲಕ್ಷಗಳ ಅನುದಾನವನ್ನು ಈ ಕಾಮಗಾರಿಗೆ ಮೀಸಲಿರಿಸಲಾಗಿರುತ್ತದೆ.

ಸದರಿ ಅನುದಾನಕ್ಕೆ 2018–19ನೇ ಸಾ ಲಿನ ಲೋಕೋಪಯೋಗಿ ಇಲಾಖೆಯ ದರಪಟ್ಟಿ ಮತ್ತು ಮಾರುಕಟ್ಟೆ ದರಗಳ ಅನುಸಾರ ಈ ಕೆಳಕಂಡ ಅಂಶಗಳೊಂದಿಗೆ ಅಂದಾಜು ಪಟ್ಟಿಯನ್ನು ರೂ.5.00 ಲಕ್ಷಗಳಿಗೆ ತಯಾರಿಸಲಾಗಿದೆ.

1. Earth Work Exavation.
2. Supplying fixing precast reinforcement concrete slabs 10cm thick.

ಸಹಾಯಕ ಅಭಿಯಂತರರು
ವಾರ್ಡ್ ಸಂಖ್ಯೆ. 15

ಸಹಾಯಕ ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ದಾಸರಹಳ್ಳಿ ಉಪ – ವಿಭಾಗ

BRUHAT BENGALURU MAHANAGARA PALIKE

Name of Work:- Road and Footpath maintenance in ward no.15 in Dasarahalli

Estimated Cost Rs.5.00 Lakhs.

Sl No	Description of work	No	Dimensions L	B	D	Qty	Rate	Unit	Amount
1	KSRB 2-2 : Earthwork excavation by manual means for foundation of buildings, water supply and sanitary lines and electrical conduits etc, either in pits or in trenches 1.5m and above in width, in soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. including breaking of clods complete as per specifications. Page No. 6/ Item No. 2.3/ PWD SR 2018-19								
	Dasarahalli main Roads & Cross Roads.	1	400.00	0.60	0.30	72.00			
						72.00	**316.94**	**Cum**	**22820.00**
	Basic Rate	299.00							
	Add Area Weightage 6%	17.94							
	Total	316.94							
2	Supplying fixing precast reinforement concrete slabs 10cm thick including cost of reinforecemet as per design and drawing material cost transpotation hire charges of machinery. Machine cutting the vertical face to get plain even surface etc., complete with all leads and lift conveyance charges labour charges of cost of all materials. Data rate approved by CE. DZ								
		1	278.00	0.90		250.20			
	Data Rates Approved					**250.20**	**1615.00**	**Sqm**	**404073.00**
							Sub total		**426893.00**
							GST Charges 12%		**51227.00**
							Tender Premium		**21345.00**
							Miscellaneous and unforseen Charges		**535.00**
							TOTAL		**500000.00**

ADMINISTRATIVELY SANCTIONED FOR 5.00 lakhs.
(Rupees Five lakhs .....)
Under the Head of Account P-3296

Technically Sanctioned for Rs. 5.00 lakhs
Rs In words five lakhs only.
Under P-3296
Job Code No 015-20-000081
Registered as CE No / Subject
to conditions contained in Enclosed Memo
No EE/DD/TS/25/20-21 Dt 17/07/2020
AE/JE Exec. Engineer

(Rupees five Lakhs Only)

Registered as no EE/D.D./AS. 104/20-21 Subject
to conditions contained in Enclosed Memo
No. EE/DD/TS/25/20-21 Dt 17/07/20
JE/AE DASARAHALLI Exec. Engineer

Certificate:

1. The work spot has been inspected and found to be necessary
2. The work spot comes under BBMP Limits
3. The provisions made in the estimate are necessary and minimum
4. The Work is not Split Up
5. This Estimate is Prepared as per KPWD SR for Bangalore Circle Electrical SR-2018-19

Assistant Engineer
Ward No.15

Assistant Executive Engineer
Dasarahalli Sub-Division
Dasarahalli Zone

Executive Engineer
Dasarahalli Division
BBMP, Bengaluru